

കൃഷ്ടേഷൻ/ടെണ്ടർ നോട്ടീസ്

നമ്പർ. IRTC/NP/02/2024 - 25 തീയതി 07 - 01 - 2025

2024 - 2025 നോൺ പ്ലാൻ ഗ്രാന്റ് പദ്ധതിയിൽ ഉൾപ്പെടുത്തി നടപ്പാക്കുന്ന “ഡോർമെറ്ററി, ഹോസ്റ്റൽ, ഫിഷറീസ് ഓഫീസ്, ക്യാർട്ടേഴ്സ് അറ്റാച്ച്മെന്റ്” പ്രവൃത്തി നിർവ്വഹണം നടത്തുന്നതിനായി അംഗീകൃത കരാറുകാരിൽ നിന്നും കൃഷ്ടേഷനുകൾ ക്ഷണിക്കുന്നു.

കൃഷ്ടേഷനുകൾ ലഭിക്കേണ്ട അവസാന തീയതി 15 - 01 - 2025 വൈകുന്നേരം 5 മണി.

വിശദാംശങ്ങൾക്ക് പ്രവൃത്തിദിവസങ്ങളിൽ ഐ.ആർ.ടി.സി. ഓഫീസുമായി ബന്ധപ്പെടാവുന്നതാണ്. ടെണ്ടറുകൾ അയക്കേണ്ട മേൽ വിലാസം : രജിസ്ട്രാർ, ഐ.ആർ.ടി.സി, മുണ്ടൂർ, പാലക്കാട് - 678592 ഫോൺ : 0491 2832663, 9188183296


രജിസ്ട്രാർ

Registrar
Integrated Rural Technology Centre
Mundur, Palakkad - 678 592
Kerala



APPENDIX A

TENDER SCHEDULE

Name of work : Repair work of Weaknd roof slab - Providing and laying of M 50 Grade Mirco concrete layer below weakned slab (6m x 5m) for retrofitting.

Approximate Quantity		Description of Items of work	Unit	Rate inclusive of GST	Amount	Amount in Words
SI No.	Quantity					
1	30	PROVIDING AND LAYING OF MIRCO CONCRETE - M50 BEAM AND SLAB BOTTOM AREA IN FIRST FLOOR AREA GRADE M50 (Highly fluid to allow for placement without vibration. Pre-packed to overcome sitebatched variations. Rapid strength gain to facilitate early reinstatement. High ultimate strengths and low permeability of cured repair. Contains no chloride admixture.)) 10cm thick.	Sqm			
2	30	SURFACE PREPARATION (SUBSTRATE BY CHIPPING OFF BEAM PLASTER, GRINDING, REMOVING UNDULATIONS/LOOSE CONCRETE COVER COAT WITH ANTI-CORROSIVE PRIMAR FILLING WHEREVER NECESSARY TO GET A LEVEL PLANE)	Sqm			
3	30	SHUTTERING FOR CONCRETE (BEAM AND SLAB AREA)	Sqm			
4	150	REBAR FIXING (CHARGES FOR PROVIDING AND FIXING OF Rebar of 8/10 MMREBAR BY DRILLING A HOLE OF 10/12 MM DIA AND DEPTH UPTO100 MM ON BEAM USING HILI RE 10 CHEMICAL USING ALL TOOLS AND TACKLES COMPLETE(FOR SHEAR KEYS BETWEEN OLD AND NEW CONCRETE))	Nos			

5	525	REINFORCEMENT WORK FOR RCC (WC002004) (Supplying and fixing steel reinforcement of Fe 415 grade for RCC as per relevant IS including transporting, storing, de-coiling, straightening, cutting, bending, spirally hooping and placing in position at all levels, all labour, equipments, incidentals, sampling and testing as prescribed in IS codes including all charges thereon for requisite tests, supervision, providing and binding with approved quality of 18G binding wire, providing and fixing PVC cover blocks, etc., complete as per drawings and specifications.)	Kg			
6	50	Providing and fixing support for existing slab in the time of concreting (SUPPORT THE GROUND LEVEL SLAB)	Nos			
Total Amount In Words						
Signature of the tenderer Name and address						